Tentative Interim Amendment

NFPA® 1225

Standard for Emergency Services Communications

2022 Edition

Reference: 18.12.1.1
TIA 22-2
(SC 21-8-44 / TIA Log #1584)

Note: Text of the TIA was issued and approved for incorporation into the document prior to printing.

1. *Revise paragraph 18.12.1.1 to read as follows:*
   18.12 System Components.
   18.12.1* Component Approval, Certification, and Listing.
   18.12.1.1 RF-emitting devices and cabling used in the installation of in-building emergency responder communications enhancement systems shall be approved by the AHJ and the frequency license holder.

Issue Date: August 26, 2021

Effective Date: September 15, 2021

(Note: For further information on NFPA Codes and Standards, please see www.nfpa.org/docinfo**)**
Copyright © 2021 All Rights Reserved
NATIONAL FIRE PROTECTION ASSOCIATION